






# Landscape Storm Water Pollution Plan General Notes

300 N. Flower Street

 714.667.8888

 714.667.8885

 [ocpCustomerCare@ocpw.ocgov.com](mailto:ocpCustomerCare@ocpw.ocgov.com) | [www.ocplanning.net](http://www.ocplanning.net)

1. Every effort should be made to eliminate the discharge of no-storm water from the project site at all times.
2. Eroded sediments and other pollutants must be retained on-site and may not be transported from the site via sheet flow, swales, area drains, natural drainage courses or wind.
3. Stockpiles of earth and other construction related to materials must be protected from being transported from the site by forces of wind or water.
4. Fuels, oils, solvents and other toxic materials must be stored in accordance with their listing and are not to contaminate the soil or surface waters. All approved storage containers are to be protected from weather. Spills must be cleaned up immediately and disposed of in a proper manner. Spills may not be washed into the drainage system.
5. Excess or water concrete may not be washed into the public way or any other drainage system. Provisions shall be made to retain concrete wastes on-site until they can be disposed of as solid waste.
6. Trash and construction related solid wastes must be deposited into a covered receptacle to prevent contamination of rainwater and dispersal by wind.
7. Sediments and other materials may not be tracked from the site by vehicle traffic. The construction entrance roadways must be stabilized so as to inhibit sediments from being deposited into the public way. Accidental depositions must be swept up immediately and may not be washed down by rain or other means.
8. Any slopes with disturbed soils or denuded of vegetation must be stabilized so as to inhibit erosion by wind or water.